



/ DHL – TIEL (NL)

CLIENT

Eurinpro

PROJECT DESCRIPTION

Realization of an entire distribution center of 18,600m²

Foundation: 2550 HSP piles underneath the warehouse floor slab 510 piles supporting the foundations.

Structure: 650 tons of steel structure 2040 m² slabs.

Concrete floor: 18,700 m² on HS-piles 5,980m² loading dock floors.

Loading bays: 36 docks.



